



ADDENDUM #1

RFP # 19-003

RFP for Josey Ranch Field 6 Adaptive Sports Field

December 8, 2018

The following changes/clarifications have been made; This Addendum forms a part of the Contract Documents and modifies, amends, deletes and/or adds to the Drawings and Project Manual as follows:

1. The Due date and time of this RFP is not changed, the **RFP is due Thursday, December 13, 2018 @ 11:30 AM.**
2. **Item #1 Perimeter Storm Sewer Line - Clarification**
The Contractor will not be responsible for furnishing and installing the perimeter drain line within the adaptive sports field. The Contractor shall install Storm Sewer Line A from STA 0 + 00 to STA 1 + 52.262 including the installation of the 12" – 45 Degree Factory Bend at the ending station. The perimeter storm sewer line shall be included within the Buy Board Item.
3. **Item #2 Unit Pricing within the Bid Form - Clarification**
The unit pricing listed within the bid form is for adjusting the quantity of materials indicated on the plans. They are for addition and deletion to the project scope only; therefore, the price given within the bid form shall be the cost for one of each of the unit price items listed within the bid form.
4. **Item #3 Fencing Detail - Clarification**
Some of the fencing details indicate that concrete flatwork pavement needs to be poured. Bidders will not be required to pour new concrete flatwork pavement. Bidders will be required to pour concrete footings for the new backstop, dugout and fence posts and associated concrete pavement for patching the cutouts in the existing pavement. For Alternate #1 (as delineated on Sheet SP-2) the contractor will be required to construct a new 15' tall backstop per Details 1&4/CD-4 and the adjoining concrete flatwork pavement necessary to patch the plaza pavement.

*****THIS ADDENDUM SHOULD BE RETURNED WITH THE ORIGINAL RFP *****

PLEASE COMPLETE THE INFORMATION BELOW:

SIGNATURE

DATE

PRINTED NAME

TITLE

COMPANY

MAILING ADDRESS

PHONE NUMBER

FAX NUMBER

E-MAIL ADDRESS